	Sub-q	Sub-quote: '303230590'CEN 230588'Q01'1'- (Write-protected) - DG08V1600B2N - Ut				
	Structu	Config	Specification Text	Application	Emergency Standby (3D)	
	ral	uration		Frequency	60 Hz	
1	1	1,	System Configuration	Generator Voltage	480 V	
2	1.1	1,	System Description	Phase	3 Phase	
4		1,	DG08V1600B2N DS400 wo / Tank	Unit Specification IBC Seismic Certification	UL2200 Without IBC	
5		1,	Application 60Hz Standby	OSHPD Certification	Without OSHPD	
6	1.2	1,	Cooling System	Engine Model	8V1600 G80S (24volts)	
0	1.2			Exhaust Emissions (EPA)	EPA Tier 3	
10		1,	50 Deg C Cooling System	Radiator Design Temperature	50°C	
10			-Closed loop, liquid cooled, with radiator factory mounted on engine-ge integral engine-driven coolant pump	Temp Rise	130°	
40	1.3	4	Circuit Breaker	Power Output	400 kW	
13	1.3	1,		Full Load Amps	601	
30		1,	Circuit Breaker Position 1:	Generator Frame and Wire Qty	433/6220 (12 Wire)	
34		1,	600 Amp 3 Pole 100% CB SQ-D PGL36060CU31A	Generator Wire Configuration	Wye	
		1,	LI Trip Breaker:	OPU/HSD	Level 1 - Standard	
41			·LI breakers provide protection from long time overload and instantane	Fuel Tank	Without Fuel Tank	
			overload current values and time delays vary with breaker type and trip	Control panel	With Control Panel	
				Circuit Breaker Options	Single Circuit Breaker	
45		1,	Circuit Breaker Mounted Right Side	Breaker Wire Color Scheme Paralleling	Standard Breaker Wire Color Scheme	
					No Parallel Operation	
59		1,	Circuit Breaker #1 Accessories:	Acceptance testing Cover photo	Factory acceptance 1/33046	
		1,	Standard Breaker Wire Scheme:	Country of Operation	USA / Canada	
			Phase 1 (A) is Black label "L1"	Emission cert, authority	18 US EPA Agency	
82			Phase 2 (B) is Red label "L2"		- To do El A Aguiley	
02			Phase 3 (C) is Blue label "L3"			
			Neutral is White label "NEU"			
84	1.4	1,	Starting System			
90		1,	Battery Rack Only			
			-Shipped with Battery Rack only (no battery included)			
98		1,	Battery Charger: NRG 22-10-RCLS			
		1,	Battery Charger Mounted & AC/DC Wired			
99			*Note* - This option will be factory-wired to the distribution panel (if sele	ected)		
		1,	Coolant Preheater			
			20 Deg F Coolant Preheater (208V 1PH - 4000W)			
108			-Model: CL140810-200			
100			-Qty 1			
			All water heaters have the AC connection wired to the distribution pane	l (if distribution panel is s	elected on	
			order) EXCEPT for 480V or 3 phase water heaters.			
113	1.5	1,	Genset Enclosure			
		1,	Level 1			
			Weather-protective enclosure constructed of heavy gauge steel or alum			
118			designed for 130 mph wind load rating. Enclosure consists of a bolted a			
			unit-mounted internal silencer included. Hinged, lockable double-door a	access on both sides of th	ne	
			enclosure.			
120		1,	Weather Proof Enclosure - Steel			
126		1,	130mph Wind Rated Steel			
139		1,	Intake Louver (Steel)			
148	1.6	1,	Vibration Isolation			
		1,	SUA46908 Pad Isolators			
154		'	• ¼ inch thick elastomeric pad in rectangular shape placed under the ba	se frame at each of the pi	re-drilled	
			isolator mounting holes			
156	2	1,	Engine Configuration			
	2.1	1,	Engine System			
161		1,	EPA Certification Tier Level: Tier 3			
162	0.0	1,	Engine Model: MTU 8V1600G80S			
164	2.2	1,	Exhaust System			
		1,	Unit-Mounted Silencer 6"			
175			Silencer Model: CPJS-06X-90031273 (RH)			
			-Silencer Model: CPJS-06X-90041272 (LH)			
			Oty 1 each			
	2.3	1, ح	FUEL SYSTEM			
184		1, Ç	No Fuel Tank 2			
187		1, 🔽	No Fuel Cooler			
195	2.4	1,	Air Intake System			
198		1,	Air Filter (Standard)			
.55		1,	MTU Air Filter			
199		١,	-SUA86885			
133			-Qty 2			
201	3	1,	Generator Configuration			
			-			
	3.1	1,	Generator system			
	3.2	1,	Generator accessories			
215		1,	Generator Model Number: 433PSL7520 (Base Model: 433CSL6220)			
44.44	40 44 5	1 2010				

11:41:10-14.01.2019

	Sub-qu	uote: '30	03230590'CEN 230588'Q01'1'- (Write-protected) - DG08V1600B2N - Unfinished
	Structu		Specification Text
	ral	uration	
		1,	PMG with DVR 2000E+
220			• True RMS Sensing - One or Three Phase Connect. Senses 95 to 600 volts ±10% at 50/60 Hertz. Patented
			circuitry senses true RMS voltage rather than average for superior load regulation.
233		1,	Measuring CT
239	4	1,	Control Panel Configuration
240	4.1	1,	USMKT_S1600_REV2-0418-CONTROL PANEL SYSTEM
249		1,	Circuit Breaker Position 1:
252		1,	Without Ground Fault
		1,	Control Panel Mounted LH Side
280			
			(4) Relay Option
			The 4-relay board includes (4) 10 amp form C relays customizable for user defined functionality
285			requirements. Standard outputs are as follows:  1. Engine Run
200			2. Engine Run
			3. Engine Fail
			4. Minor Alarm
289		1,	Remote E-Stop
		1,	MGC- 2000 Series
			-MTU Onsite Energy's Digital Genset Controller MGC-2000 series is a highly advanced integrated
			generator set control system. The MGC-2000 series is perfectly focused, combining rugged construction
310			and microprocessor technology to offer a product that will hold up to almost any environment and flexible enough to meet your application's needs. This device provides generator set control, transfer switch
			control, metering, protection, and programmable logic in a simple, easy-to-use, reliable, rugged, and cost
			effective package.
319		1,	No Parallel Operation
324	5	1,	Services and After Sales Supply
325	5.1	1,	Warranty
		1,	General Terms and Conditions of Sale, Warranty and After Sales Supply
			Our offer is based on the attached General Terms and Conditions of Sale for MTU Products (Rev.
328			V-601-1803 MUS & MOE) and the Warranty will be the attached Standard Two (2) Year / 3,000 Hour Basic
020			Standby (3D), Prime (3B), and Data Center Continuous Power (DCCP) (3F) Limited Warranty
			(OE-M-GEN-S-026-1801).
329	6	1,	Miscellaneous
330			
339	0.1	1,	Painting
			Paint Color: RAL 7001 Grey
343	6.2	1,	Documentation
347			English 1 CD Manual (Standard)
349		1,	Optional Manuals
352			English
354			No CD Format
356			1 Hard Copy
360			No Flash Drive
362			French
364		_	No CD Format
366			No Hard Copy
368			No Flash Drive
370			Spanish
372			No CD Format
374			No Hard Copy
376			No Flash Drive
377	6.3		Additional Options
392		1,	Fuel Water Separator Mounted RH Side
454	7	1,	Functional Testing
455	7.1		Acceptance Testing
458			Standard Commercial Test
	8		Shipping Conditions
	8.1		Shipment
497			Ship unit with fluids installed
731	L	٠,	Pring and the mediane

11:41:10-14.01.2019 2